

MARSEILLE  
DU 27 MAI  
AU 3 JUIN  
**2022**



ICOLD  
27<sup>TH</sup> CONGRESS  
90<sup>TH</sup> ANNUAL  
MEETING



CIGB  
27<sup>ÈME</sup> CONGRÈS  
90<sup>ÈME</sup> RÉUNION  
ANNUELLE



## Embankment Dam Committee E Workshop

# Standard Proctor water content variation

**Danie Badenhorst**  
**SANCOLD, AECOM**





## Standard Proctor Water Variance Specification

Water content variance from Optimum (%)	Application	Zone of Earthfill Dam
0 to 2	Impervious earthfill Materials	Core
-1 to 3	Semi-pervious earthfill Materials	Outer Zone



## Embankment Dam Committee E Workshop

### 1 Introduction

- Location of core and outer zones of a zoned earthfill dam
- Definition of semi-pervious and impervious earthfill materials
- Water content variance specification

### 2 Standard Proctor Compaction Test Definition

### 3 Specification of Water content variation


### 4 Driekloof Dam shear strength testing

- Results

### 5 Conclusions



## Core and Outer Zone Materials







## Definition of Impervious and Semi-pervious Earthfill Materials


Geomechanical Property	Zone of earthfill dam	
	Core (Impervious materials)	Outer Zones (Semi-pervious Materials)
Grading	> 60% through 0.42 sieve	> 40% through 0.42 sieve
Clay content (CC) (%)	10<CC<30	CC<10
Liquid Limit (LL) (%)	30<LL<60	LL<30
Plasticity Index (PI)	12<PI<35	4<PI<12.5
Linear Shrinkage (LS) (%)	40<LS<10	7<LS<0
Maximum Dry Density (MDD) (kg/m <sup>3</sup> )	1 450<MDD<1 880	1 750<MDD<2 100
Optimum Water Content (w) (%)	14<w<25	6<w<16
Shear strength (°)	18<Phi'<30	28<Phi'<38
Cohesion (C) (kPa)	12<C'<24	C'<12
Permeability (k) (cm/s)	k<10 <sup>-04</sup>	K>10 <sup>-04</sup>



## Design for a seal (Core) in an embankment dam

- Elasticity is important to prevent cracking
- Casagrande study showed compaction by Standard Proctor facilitate this
- Elasticity in core more important than in outer zones

## Compaction Standards





## Test references and Details

Test	Reference	Mould diameter (mm)	Hammer mass (kg)	Fall height of hammer (mm)
Standard Proctor	ASTM D698 AASHTO T99	100	2.5	304
Modified AASHTO or Modified Proctor	D1557, AASHTO T180	100	4.54	457.2





## **Driekloof Dam in South Africa**

**Laboratory triaxial shear strength testing with volume change of soil samples**

Property	Impervious Earthfill	Semi-pervious Earthfill
Phi	<p>NOTE: Uncontrolled, undrained test results.</p> <ul style="list-style-type: none"> <li>Graph for Compaction Standard ①</li> <li>Graph for Compaction Standard ②</li> <li>Graph for Compaction Standard ③</li> </ul>	<p>NOTE: Uncontrolled, undrained test results.</p> <ul style="list-style-type: none"> <li>Graph for Compaction Standard ①</li> <li>Graph for Compaction Standard ②</li> <li>Graph for Compaction Standard ③</li> </ul>
C	<p>NOTE: Uncontrolled, undrained test results.</p> <ul style="list-style-type: none"> <li>Graph for Compaction Standard ①</li> <li>Graph for Compaction Standard ②</li> <li>Graph for Compaction Standard ③</li> </ul>	<p>NOTE: Uncontrolled, undrained test results.</p> <ul style="list-style-type: none"> <li>Graph for Compaction Standard ①</li> <li>Graph for Compaction Standard ②</li> <li>Graph for Compaction Standard ③</li> </ul>

Property	Impervious Earthfill	Semi-pervious Earthfill
Ei 100KPa	<p>Graph showing Dry Density (<math>\text{kg/m}^3</math>) vs Moisture Content (%) for Impervious Earthfill at <math>E_i</math> at <math>\sigma_3 = 100 \text{ kPa}</math>. The graph includes curves for Compaction Standard 1 (red), Standard 2 (blue), and Standard 3 (green). A dashed line indicates the 100% Saturation line. A note specifies '0 to 2% Above Optimum'.</p>	<p>Graph showing Dry Density (<math>\text{kg/m}^3</math>) vs Moisture Content (%) for Semi-pervious Earthfill at <math>E_i</math> at <math>\sigma_3 = 100 \text{ kPa}</math>. The graph includes curves for Compaction Standard 1 (red), Standard 2 (blue), and Standard 3 (green). A dashed line indicates the 100% Saturation line. A note specifies '-1% to 3% Above Optimum'.</p>
Ei 200kPa	<p>Graph showing Dry Density (<math>\text{kg/m}^3</math>) vs Moisture Content (%) for Impervious Earthfill at <math>E_i</math> at <math>\sigma_3 = 200 \text{ kPa}</math>. The graph includes curves for Compaction Standard 1 (red), Standard 2 (blue), and Standard 3 (green). A dashed line indicates the 100% Saturation line. A note specifies '0 to 2% Above Optimum'.</p>	<p>Graph showing Dry Density (<math>\text{kg/m}^3</math>) vs Moisture Content (%) for Semi-pervious Earthfill at <math>E_i</math> at <math>\sigma_3 = 200 \text{ kPa}</math>. The graph includes curves for Compaction Standard 1 (red), Standard 2 (blue), and Standard 3 (green). A dashed line indicates the 100% Saturation line. A note specifies '-1% to 3% Above Optimum'.</p>
Ei 400Kpa	<p>Graph showing Dry Density (<math>\text{kg/m}^3</math>) vs Moisture Content (%) for Impervious Earthfill at <math>E_i</math> at <math>\sigma_3 = 400 \text{ kPa}</math>. The graph includes curves for Compaction Standard 1 (red), Standard 2 (blue), and Standard 3 (green). A dashed line indicates the 100% Saturation line. A note specifies '0 to 2% Above Optimum'.</p>	<p>Graph showing Dry Density (<math>\text{kg/m}^3</math>) vs Moisture Content (%) for Semi-pervious Earthfill at <math>E_i</math> at <math>\sigma_3 = 400 \text{ kPa}</math>. The graph includes curves for Compaction Standard 1 (red), Standard 2 (blue), and Standard 3 (green). A dashed line indicates the 100% Saturation line. A note specifies '-1% to 3% Above Optimum'.</p>





## Geomechanical characteristics for water content variance

Property	Water content variance (%)	
	0 < w < 2 (Impervious Earthfill)	-1 < w < 3 Semi-pervious Earthfill
Shear Strength (Phi) (Degrees)	1 to 8	30 to 33
Cohesion (C) (kPa)	+30 to 90	52 to 55
Ei Modulus (MPa) (Sigma 3 = 100 kPa)	2 to 10	10 to 62
Ei Modulus (MPa) (Sigma 3 = 200kPa)	2 to 15	15 to 92
Ei Modulus (MPa) (Sigma 3 = 400kPa)	2 to 25	20 to 135





**Placement  $0\% < w < 2\%$   
(Impervious core earthfill)**

Shear strength  $\Phi$  and  $C$  vary more – but not so important for Embankment slope stability

$E_i$  varies very little and less than for semi-pervious materials. (no cracking of core)

**Placement  $-1\% < w < 3\%$   
(Semi-pervious outer zone earthfill)**

Shear strength  $\Phi$  and  $C$  variation is low which is important for Embankment slope stability

Significant variance more than for impervious soils on  $E_i$ . Elasticity less important for outer zones.



From the above the following can be concluded:

- The Standard Proctor compaction standard should be used for compaction of earthfill in embankment dams.
- As zoning for earthfill embankment dams into a central core and outer zones with impervious and semi-pervious earthfill used in the respective zones, the variation of water content during compaction of the zone materials into 0% to 2% and -1% to 3% of the optimum water content for the respective core and outer zones, **provides the required geomechanical parameters for earthfill**; and
- provided the basis at Driekloof Dam for a design **meeting elasticity and no cracking requirements**.



**Thank you**